


GENERAL NOTES



1. CONTRACTORS ARE TO EXAMINE THIS SITE AND DOCUMENTS OF OTHER TRADES, AND BECOME FAMILIAR WITH THE FULL SCOPE OF WORK.
2. INSTALL ALL PLUMBING WITHIN FRAMED WALLS, CHASES, OR TIGHT TO STRUCTURE UNLESS NOTED OTHERWISE. NO WATER PIPING SHALL BE INSTALLED IN THE ATTIC SPACE.
3. COORDINATE LOCATIONS AND REQUIREMENTS WITH OTHER TRADES PRIOR TO FABRICATION OF MATERIALS. PLAN OFFSETS AS REQ'D TO AVOID CONFLICTS WITH DUCTWORK AND STRUCTURE.

KEYED NOTES

1. INSTALL NEW 1/2" DOMESTIC WATER SERVICE FROM THE STREET MIN 1 FT DEEP. COORDINATE EXACT MATERIAL AND LOCATION WITH CIVIL. NEW WATER LINE SHALL ENTER THE BUILDING JUST ABOVE THE EXISTING WALL FOOTER. PROVIDE A LINK SEAL AROUND WALL PENETRATION.
2. INSTALL NEW 1" FIRE PROTECTION WATER SERVICE FROM THE STREET MIN 1 FT DEEP. COORDINATE EXACT MATERIAL AND LOCATION WITH CIVIL. NEW WATER LINE SHALL ENTER THE BUILDING JUST ABOVE THE EXISTING WALL FOOTER. PROVIDE A LINK SEAL AROUND WALL PENETRATION.
3. OFFSET AND ROUTE 1" FIRE PROTECTION LINE UP. LOCATE PIPING HIGH AND TIGHT TO THE CEILING AND THE BEAM OVER TO THE FIRE PUMP ROOM.
4. SEE FIRE PROTECTION SPECS FOR THE ROOM LAYOUT AND INSTALLATION. ALL WALL IN THIS ROOM HAVE A 1 HOUR RATING.
5. ROUTE 1/2" CW DOMESTIC LINE FROM THE WATER METER HIGH AND TIGHT AROUND THE PERIMETER OF THE ROOM TO THE BOOSTER PUMP AS SHOWN.
6. ROUTE DOMESTIC WATER LINES UP IN 2 HOUR CHASE TO SERVE THE REST OF THE BUILDING. SEAL PENETRATION AS REQ'D. SEE BASEMENT SHEET FOR CONTINUATION.
7. INSTALL 3/4" HDV AND CW DOMESTIC WATER LINES DOWN TO LAUNDRY SINK EXPOSED. SUPPORT WITH LINK-STRUT AND CLAMPS AS REQ'D.
8. DO NOT INSTALL DOMESTIC WATER OF ANY KIND IN THIS ROOM.



**OLD STONEY REMODEL
PHASE ONE
108 NORTH 4TH STREET
SUNDANCE WY, 82729**



PROJECT NUMBER
16-022 / 17040

DATE
11/20/2017

DRAWN BY
AE/KRD

DISK ID.

SHEET TITLE
PHASE 1
SUB-BASEMENT
FLOOR PLAN -
DOMESTIC PIPING

SHEET NUMBER

15.20