GENERAL NOTES

- EXT'G CONDITIONS ARE BASED ON AVAILABLE INFORMATION. PRIOR TO SUBMITTING A BID, THE CONTRACTOR SHALL VISIT THE SITE TO VERIFY ALL CONDITIONS AND DIMENSIONS. NO EXTRAS WILL BE GIVEN FOR FAILURE TO INVESTIGATE.
- 2. MEANS AND METHODS ARE THE RESPONSIBILITY OF THE CONTRACTOR. INCLUDE FOR A COMPLETE INSTALLATION WITHOUT ADDITIONAL COST TO THE OWNER.
- 3. FIELD ORGANIZE AND INSTALL ALL EQUIPMENT, DUCTWORK, PIPING, CONDUIT, ETC FOR MAXIMUM CLEARANCE AND MAINTENANCE ACCESSIBILITY. (ALL TRADES)
- 4. EXISTING PIPING, DUCTWORK AND EQUIPMENT SHOWN LIGHT. NEW PIPING, DUCTWORK AND EQUIPMENT SHOWN BOLD.
- 5. EXISTING PIPING, DUCTWORK AND EQUIPMENT TO REMAIN OR THAT WHICH IS NOTED TO BE REUSED SHALL BE PROTECTED FROM DAMAGE.

KEY NOTES

EXISTING REFRIGERANT PIPING UP IN WALL FRAMING FROM BELOW SERVING THE 2ND LEVEL FROM PHASE 1. CONNECT TO THESE LINES AND EXTEND OUT TO THE BRANCH SELECTOR BOXES AS SHOWN AND DETAILED.

2. FIELD VERIFY MFGR'S ACCESS INTO ALL COMPONENTS OF THE SYSTEM IN THE ATTIC PRIOR TO INSTALLATION.





SECOND FLOOR HYDRONIC PIPING

SECOND FLOOR PLAN - HYDRONIC PIPING

1/4" = 1'-0" 01